WATER SUPPLY DIVISION.

Dated 21st October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water-supply Division, up to 14th November 1930, till 1 P.M. for laying 4" Cast Iron delivery and distribution pipes for Water-supply to the northern extension and Kuripalya, at Tumkur. An approximate estimate of quantities is given below.- These quantities are not guaranteed. The work should be completed by the end of 31st March 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engine Office at Water-supply Division, between the hours of 11 to 5 P.M. Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 225 only in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tender for Laying 4" Cast Iron delivery and distribution pipes for Water-supply to northern extension and Kuripalya at Tumkur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate of quantities for laying 4" Cast Iron delivery and distribution pipes for Water-supply to northern extension and Kuripalya Tumkur.

No.	Items of work	Per	Quantity
	NORTHERN EXTENSION LABOUR.		
1	Earthwork excavation for laying and jointing 4" C. I. pipes and refilling trench.	C.yd.	2,045
2	Laying and jointing with cement 4" pipes including cutting fixing branches, collars, etc., conveying from stores.	Joints	500
3	Do 4" lead jointing ...	"	120
4	Do 3" cement joints ...	"	130
5	Do 3" bad joints ...	"	20
6	Conveying from stones, laying and jointing 2" G. I. pipes including cuts and collar joints and also earthwork.	R.ft.	2,600
7	Fixing valves with rubber insertion bolts, nuts, etc., 4" air and sluice.	Each	2
8	Do 3" sluice value ...	"	1
9	Do 2" gland cock ...	"	1
10	Constructing valve cisterns and fixing shutters, etc., complete.	"	3
11	Constructing gland cock citerns and fixing road boxes.	"	8
12	Constructing street fountains including Cast Iron fountains.	"	6
13	Laying and jointing 1½" pipe including excavation and refilling.	R.ft.	800
14	Do do ¾" do	"	900
1	Conveying from s... cluding, cuts, collers, thre... for 2" G. I. pipes.	R.ft.	2,000
2	1½" ... and relaying	"	1,92
3	1½" ...	"	2,075
4	...	"	510
	...	Each	5
	...	"	3